



- NOTES:
1. CONTRACTOR TO VERIFY ALL DIMENSIONS. FACTORY CANNOT ASSUME ALTERATION COSTS AFTER FINAL SUBMITTAL DRAWINGS HAVE BEEN APPROVED.
 2. HOUSING, SIDE ARM TUBES, AND COUNTERWEIGHTS (12 x 12) TO BE HOT DIP GALVANIZED.
 3. STEEL OPERATOR TO HAVE DOORS IN FRONT AND BACK (ROADWAY AND COUNTERWEIGHT END).
 4. STEEL BOLLARD TO HAVE DOOR IN BACK.
 5. ONE (1) UNIT REQUIRED.
 6. GALVANIZED ANCHOR BOLTS & TEMPLATE BY B & B. ($\phi 1.125-7$ UNC X 2'-9" LONG).
 7. .875" DIAMETER CABLE TO LOOP THROUGH 4" NOM SCH 40 PIPE.
 8. .188" SS TRUSS CABLES WITH GALVANIZED TURNBUCKLES, 2 PLACES.
 9. BARRIER ARM TO HAVE RED & WHITE REFLECTIVE STRIPES 16" WIDE AT 45°.

CUSTOMER
CR-25M Barrier
DIM A = 22'-4"

B&B ARMR
 2009 Chenault Dr #114
 Carrollton, Tx 75006
 800-367-0387